

145
1881 (CA)

"Comfortable & Warm in Winter"



TELEPHONES.
PUTNEY 4027 & 2771.

TELEGRAMS.
SWACOBUNGA, WALGREE

"Delightfully Cool in Summer"

The South Western Appliance Co. Ltd
High Street,
Fulham. s.w.6

The Bungalow Specialists

REGISTERED TRADE MARK





Digitized by the Internet Archive
in 2020 with funding from
Columbia University Libraries

<https://archive.org/details/bungalowspeciali00sout>

SPECIAL NOTES.

1-in. T. & G. Weather Board.—A special feature of this material is that it is perfectly weathertight owing to the fact that the joint was designed to keep out draught as well as water, and each board is individually fixed.



Window and Door Frames.—The door and window frames used in our Bungalows are of the rebate ovolo type, this being manufactured out of the solid. It makes the doors and windows perfectly wind and weather proof.

Sashes and Joinery.—Of the best quality. Sashes mortised and tenoned ovolo type, ensuring a perfect job used in conjunction with our solid moulded frames.

TERMS OF PURCHASE.

1. Half the cost of building with Order.
2. Balance when building is ready for despatch in the Sellers yards.
3. Cash with all orders under £20.
4. When balance purchase money received from buyer, the Sellers will cause every building or section or parts of such building to be despatched in accordance with the requirements of the buyer at his risk, but the sellers will pay carriage to railway station England and Wales. The Sellers will at all times use their best endeavours to ensure prompt delivery.
5. The Sellers shall not be held liable for non-delivery or delay in the delivery of any building or section or part of such building caused directly or indirectly by strikes, lock-outs, etc., in the building trades or on the Railways.

OLYMPIA BUNGALOW, 1925




South Western Appliance Co. Ltd.

price


£175

NETT




→ You may have choice of these three different interiors.

As an additional advantage in the construction of this Bungalow, we have included our original Leaded Light Windows, as per circular sketch, without increase of price.



South Western Appliance Co. Ltd.
(copyright)




"OLYMPIA" BUNGALOW (1926)

£198 : 15 : 0


Carriage paid throughout England and Wales. (No Extras)

Constructed by
The South Western Appliance Co., Ltd.
HIGH STREET, FULHAM, S.W.6

Telephones: Putney 4027 & 2771. Telegrams: "Swacobunga, Walgreen."




FRONT ENTRANCE



PLAN SCALE $\frac{1}{8}$ IN TO FT
of FOUNDATIONS (1926) "OLYMPIA"
BUNGALOW.

NOTE = WE HAVE SHOWN HERE ALL NECESSARY BRICK OR CONCRETE PIERS, BUT IF DESIRED A DWARF WALL MAY BE BUILT ALL ROUND UNDER OUTSIDE WALLS, THE DWARF WALL MAY BE INSISTED UPON, BY CERTAIN BOROUGH OR DISTRICT COUNCILS.





(See Illustration and Ceiling Plan on page 43.)

OLYMPIA BUNGALOW. 1926.

IN drawing attention to one of our latest productions, the 1926 Bungalow exhibited at the "Daily Mail" Ideal Homes Exhibition, 1926, we wish to point out that this is brought up to the highest standard of excellence, combined with the best possible value.

The outstanding features of which are: Price **£198 15s. 0d.** In general appearance the Bungalow closely resembles a permanent building of the Tudor period (though merely a portable building).

Walls.—Are clad with 1" Tongued and Grooved Weather boards for the lower part and Rough Cast Asbestos for the upper sections, thus giving a substantial effect which is also damp proof and weather resisting. Inside walls Plain Asbestos Sheets with overlays.



Accommodation.—Six large rooms, Bath Room and W.C., together with a departure from the usual type of Verandah being of the Loggia style.

Entrance.—A unique (copyright) design with leaded lights on either side and fanlight over door.

Store Room.—Light is introduced through a decorative Dormer window into storage loft in roof, will be found very useful. Double Casements.

Windows.—Are ample and of good dimensions for light and air. Mortised and Tenoned Ovolo Stop stuck in the solid (not nailed on).

Sashes.—Mortised and Tenoned (moulded in the solid) fanlight to open.

Floors.—1" Tongued and Grooved 2"×3" joists.

Sleeper Plates.—3"×3" creosoted.

Partitions.—Plain asbestos sheets supplied for both sides, also for Ceilings with overlays.

Doors.—Front and Back $\frac{1}{2}$ glass, English make, 2" thick.

Inside Doors.—6' 6"×2' 6" $1\frac{1}{2}$ " solid moulded.


Roof.—Boarded $\frac{3}{4}$ " matching with Eternit Asbestos tiles for covering and half-round ridges.

Glass.—21-oz. to glaze.


Overhanging Tudor Gables are designed to keep the building dry.

The readiness with which the Bungalow may be extended or converted into a Tea House, Club Rooms, Sports Pavilion, etc., at a small cost is a strong recommendation.

The generous specifications of Material used in this structure as compared with other buildings of similar nature, together with 3" cavity walls and partitions keep the home "Warm in Winter and Cool in Summer."



NOTE: THE STRENGTH OF OUR BUNGALOWS



"The SOUTH WESTERN COTTAGE."

Specification as above—
But with plain Abestos in place of Rough Cast Sheets.

NOTE.—Although we are making another type of Bungalow to give our clients an alternative design, we think it only fair to our prospective clients to mention that the 1925 Bungalow proved our *most successful effort* in our many years experience and is to-day, perhaps, *The Best Bungalow* (size and price considered) *that has ever been made*. We also find that our competitors are imitating us as closely as their incompetent efforts will allow.

ONE OF MANY LETTERS OF APPRECIATION RECEIVED.


THE BUNGALOW,
LADMANLOW, near BUXTON,
February 25th, 1926.

Dear Sir,

I have one of your Olympian Model 1925 Bungalows, which we are very satisfied with, and I am writing to ask you if you would kindly forward me a Catalogue of Fencing, Gates and Rustic Arches.

I think that the Bungalow is wonderful value for money and has stood a Buxton winter splendidly.

Yours faithfully, GEO. NODDER.



Constructed
by

The South Western Appliance Co., Ltd.,

High Street, Fulham, S.W.6



Telephones: Putney 4027 & 2771.

Telegrams: "Swacobunga, Walgreen."


HILL'S Improved CHEMICAL CLOSET

An Ideal Natural Position Sanitary Closet.

**HEALTH IS YOUR GREATEST
ASSET, THE OLD-FASHIONED
EARTH BUCKET IS THE
CAUSE OF MANY DISEASES.**



OVOLO MOULDED
CASEMENT WINDOWS
MOULDED IN THE SOLID
MORTISED & TENONED




TONGUED & GROOVED
WEATHER BOARDS.

It will Save
you the Cost
of Building a
Cesspool.

For
Bungalows,
Schools,
Country
Houses,
Yachts, etc.,
etc.

It keeps the
Flies away.
The carriers
of Disease.



There are
No
Unpleasant
Smells.


It can be fitted
in your
Bath Room or
Outhouse.

The Chemical
is Antiseptic.
A valuable
Manure and
quite
Harmless.

It is made of Galvanized Mild Steel,
Enamelled, well Ventilated and consists of
Ventilating Chamber, Elbow, 6-ft. of
Pipe and Cowl.


PRICE Complete with ONE
GALLON OF CHEMICAL **£3 15s.**

Chemical can be obtained from your Ironmonger,
or direct from us 4/- per Gallon.




Price - **£390**

SPECIFICATION SAME AS OLYMPIA BUNGALOW 1926 (see page 5)



Price - **£245**

SPECIFICATION SAME AS OLYMPIA BUNGALOW 1926 (see page 5)




Price

£166 10SPECIFICATION SAME
AS OLYMPIA BUNGALOW

1926



South Western Appliance Co.





Fire Proof
"Cosy" Bungalow,
4 rooms.

Asbestos sheets are supplied for inside and outside of walls, also for roof or red tiles

£125

It with Patent Rough Cast Asbestos sheets for outside of walls

£137



Fire Proof
"Cosy" Bungalow.
3 rooms.

Asbestos sheets are supplied
for inside and outside of walls,
also for roof,









Price £92



If with Patent Rough Cast Asbestos
Sheets for outside of walls,

£100

"Building a Bungalow"

SIZE 40' x 14' Weather Board Walls, Lined with Asbestos Sheetting.
Built and delivered in sections.







The "COSY"
BUNGALOW,
with Four Rooms, Felt Roof,

£112

Chimneys and Foundations not
included in the price quoted.

£125

Tiles for Roof, Red or Grey.





The South Western Appliance Co. Ltd.
Registered.
Design.

Semi-Detached Bungalows


Price - **£310**

SPECIFICATION SAME AS OLYMPIA BUNGALOW 1926.





"Fulham Palace"
3 Roomed Bungalow

South Western Appliance Co. Ltd.
Registered.



Price - £80

SPECIFICATION SAME AS OLYMPIA BUNGALOW 1926



"Fulham Palace" Bungalow



Price - **£120**

SPECIFICATION SAME AS OLYMPIA BUNGALOW 1926

(See page 5)

South Western Appliance Co. Ltd.
REGISTERED.



THE "COSY" BUNGALOW.



This most economical Bungalow is matchboarded inside with tongue-grooved and beaded boards, or asbestos cement sheets supplied. Walls and all external parts with 1-in. tongued and grooved weather boards, upon 2 x 3-in. framing. Floors 1-in. tongued and grooved boards upon 2 x 3-in. joists, strong boarded roofs with "Pluvex" felt. Casement windows, 21-oz. glass, good locks and fastening, bolt, &c. Buildings treated externally with our waterproof composition. Complete and carriage paid (England and Wales) for the sum of **£85 nett.**

NO EXTRAS.

Quotations for larger or extra rooms if required.





"OLYMPIA MODEL 4-ROOM BUNGALOW"

Price with Flat Ceilings, **£140**

Bath Room and W.C., **£12 10s.**


Specification similar to 1926 Bungalow, but with outside walls all tongued and grooved weatherboards.

NO. 2 "OLYMPIA" ROUGH CAST BUNGALOW.




South Western Appliance Co.
"OLYMPIA" BUNGALOW NO. 2
1924. MODEL

4 Rooms and usual Offices, Verandah, etc., 1924 Model, Outside
Walls Rough Cast, Abestos Tiles and Ridges for Roof, £205



Price - £60




The Lounge of The Rough Cast Bungalow.








VIEW OF WORKS,
The South Western Appliance Co. Ltd.
HIGH STREET, FRONTAGE UPWARDS OF 500 FT.
FULHAM. S.W.6.




Interior of the Four-Room Cosy Bungalow.



Kitchen.

The South Western
Appliance Co., Ltd.
HIGH STREET,
FULHAM, S.W.6



Bed Room.






The "Olympia Cosy"
Bungalow
4 Rooms

"OLYMPIA" (NO. 1) 4 ROOM BUNGALOW


(RED ASBESTOS TILED ROOF.)

Price £130 complete.




Flat Ceilings.


CRICKET PAVILION




For Lining, Matching or Asbestos.




The "RICHMOND" Bungalow.



Artistic design. Portable. Built in sections. Tenant's fixtures.
Flat Ceilings. Price Complete, £115.




The "Surrey" Portable Cottage




South Western Appliance Co.

	£	s.	d.		£	s.	d.
8 × 6	9	18	0	16 × 10	26	2	0
10 × 8	12	16	6	20 × 10	31	10	0
12 × 8	15	6	0	24 × 12	45	0	0
14 × 10	23	6	0				

The "RIVERSIDE" Bungalow.




Very popular by the riverside. Built in sections to bolt together.
Flat Ceilings. Price Complete, £80.

MOTOR CAR HOUSE No. 2.


	£	s.	d.		£	s.	d.
12-ft. long × 8-ft. wide	18	0	0	18-ft. long × 10-ft. wide	32	8	0
14-ft. long × 10-ft. wide	25	4	0	20-ft. long × 12-ft. wide	43	4	0
16-ft. long × 10-ft. wide	28	16	0				

Walls and Roofs constructed of strong 2 by 3 deal framing. Walls externally clad with 1-in. Tongued and grooved weather boards and stained with weather-proof composition. Floor of 1-in. tongued and grooved boards on 3 by 2 joists. $\frac{3}{4}$ -in. tongued and grooved boarded roof covered with best Pluvex felt. If building is lined inside with matchboarding, 20 per cent. extra.

The "WALTON" MOTOR CAR HOUSE.


	£	s.	d.		£	s.	d.
8-ft. × 6-ft. ...	7	1	0	14-ft. × 10-ft. ...	18	18	0
10-ft. × 8-ft. ...	10	16	0	16-ft. × 10-ft. ...	23	0	0
12-ft. × 8-ft. ...	14	0	0	18-ft. × 12-ft. ...	28	2	0
14-ft. × 8-ft. ...	16	4	0	20-ft. × 12-ft. ...	34	0	0

Best Material. Good Workmanship. Wind and Weather proof. Tenant's Fixture.

Motor Garage With Partition. For 2 or more Cars.

14-ft. × 12-ft. ...	£25	4	0	Treated with weather-proof composition. Estimates for any specified size.
16-ft. × 12-ft. ...	32	8	0	
16-ft. × 16-ft. ...	39	16	0	

SEE SPECIFICATION (page 41).


GARDEN or ALLOTMENT SHED.

Length	Width	£	s.	d.	Length	Width	£	s.	d.
6-ft. × 4-ft. ...	...	5	18	0	9-ft. × 6-ft. ...	...	8	7	0
7-ft. × 5-ft. ...	...	6	11	0	10-ft. × 8-ft. ...	...	11	11	0
8-ft. × 6-ft. ...	...	6	18	0	Including Floor and Joist.				

A strong serviceable Shed, suitable for many purposes. Being made in sections is very easy to erect and take down. Treated with weather-proof composition. Strong boarded roof. Pluvex Felt. Bench extra if required. Walls of $\frac{3}{4}$ -in. Tongued and grooved matching.


All Goods
Carriage Paid.

The St. Helier.




No.	Length	Width	Height to ridge		Price		
	ft.	ft.	ft.	in.	£	s.	d.
1	10	8	8	0	12	17	0
2	12	8	9	0	15	11	0
3	15	9	10	0	20	14	0
4	20	10	10	0	30	16	0
5	24	12	10	0	42	11	0

SEE SPECIFICATION (page 23)



Rustic Seats

4-ft. long	...	19/-
5-ft. „	...	23/-



Rustic Summer House

6-ft. x 6-ft.


£12 12 0

“Olympia” Model Motor House

FIREPROOF.

SOUNDPROOF.

NON-ABSORBENT.



1	12-ft. x 8-ft.	...	8-ft. 6-in.	...	...	20	6	0
2	14-ft. x 10-ft.	...	9-ft. 6-in.	...	...	29	11	0
3	18-ft. x 10-ft.	...	9-ft. 6-in.	...	...	34	1	0
4	18-ft. x 10-ft.	...	10-ft. 0-in.	...	...	38	6	0
5	20-ft. x 12-ft.	...	11-ft. 0-in.	...	...	42	12	0

These Buildings are fire-resisting because of the use of **Asbestos** in the preparation of the materials of which they are constructed.

Asbestos is accepted as the most incombustible material.



“**Eternit**” **Asbestos Cement Sheets**. The successful process by which this invention is manufactured marks an epoch in Building Construction. The characteristics of this indestructible article are well known to and recommended by Architects and Surveyors of the London County Council.

“**Eternit**” is weather-tight and damp-proof, and does not shrink, swell, crack or crumble through atmospheric influences.

“**Eternit**” **Sheets** can be distempered, painted, enamelled, or papered as desired.

Prices for Buildings entirely constructed with “**Eternit**” **Asbestos Cement Slabs**.


ALL GOODS CARRIAGE PAID ENGLAND AND WALES.

BATHING HUT**PRICE - £9 10s.****Portable Automatic Earth Closet - £4 10****Portable Hut for same, 4-ft. x 3-ft. 6-in. £3 16s.**


All Goods
Carriage Paid.

Portable Hut on Wheels

8x6 ...	£8 7 0	14x10	£21 17 0
10x8 ...	14 0 0	16x10	24 16 0
12x8 ...	15 11 0	20x12	37 6 0


**Price, including Desk £9 10s**

The Beaconsfield.




No.	Length ft.	Width ft.	Price £ s. d.
1	8	6	6 16 0
2	9	7	8 12 0
3	10	8	11 11 0
4	12	8	14 13 0
5	14	10	20 0 0
6	16	10	23 11 0

The Clinton.



No.	Length ft.	Width ft.	Height to ridge ft. in.	Price £ s. d.
1	8	6	7 6	7 14 0
2	10	8	8 0	11 14 0
3	12	8	8 0	14 13 0
4	14	8	8 6	17 7 0
5	16	9	9 0	20 14 0


The "DELHOLME."



No.	Length ft.	Width ft.	Height to ridge ft. in.	Price £ s. d.
1	8	6	7 0	7 0 0
2	10	8	8 6	11 11 0
3	12	8	9 0	16 14 0
4	14	10	10 0	20 6 0
5	16	10	10 0	24 18 0
6	18	10	10 0	29 0 0
7	20	10	10 0	31 10 0
8	20	12	10 0	34 4 0


SEE SPECIFICATION (page 41).

The Rusholme.



No.	Length ft.	Width ft.	Height at back ft. in.	Height at front ft. in.	Price £ s. d.
1	6	4	6 0	5 0	6 3 0
2	8	6	7 0	6 0	7 1 0
3	10	8	8 0	7 0	11 11 0
4	12	8	8 6	7 6	14 13 0
5	14	10	8 6	7 0	20 0 0
6	16	10	9 0	7 0	24 13 0

SEE SPECIFICATION (page 41).



South Western
Appliance Co.

Double Gates, complete £8 2s.

8ft x 6., with Oak Posts.




South Western Appliance Co.


Single Gates, complete £4 10s.

3ft. 6in with Oak Posts and Fittings.

Exterior of the
Hospital for Blind
Soldiers at
Regents Park, erected
by Messrs.
The South Western
Appliance Co., of
Fulham.



The Broomwood.




No.	Length ft.	Width ft.	Height at ridge ft. in.	Price £ s. d.
1	10	8	8 6	11 14 0
2	12	8	8 6	15 3 0
3	14	10	9 0	19 16 0
4	15	10	10 0	21 4 0
5	18	12	10 0	28 16 0

SEE SPECIFICATION (page 41).

Portable Building.


Suitable for many purposes.



	£	s.	d.		£	s.	d.
8-ft. x 6-ft. ... 8-ft. ridge	7	13	0	12-ft. x 8-ft. ... 9-ft. ridge	14	3	0
9-ft. x 7-ft. ... 8-ft. "	9	18	0	14-ft. x 10-ft. ... 9½-ft. "	22	2	0
10-ft. x 8-ft. ... 8½-ft. "	12	12	0	16-ft. x 10-ft. ... 9½-ft. "	25	4	0


A strong, well-built house, treated externally with weather-proof composition.
Good Floor. — Boarded roof. — Good Pluvel Felt.

Motor Car House No. 3.




In sections to bolt together. Gutterings and pipes extra. Benches and shelves extra. Specifications and prices same as No. 2. Best class materials and workmanship only

Corrugated Iron Motor Car House.



Consequent upon the frequent fluctuations in the Iron Market, we have to give quotations, etc., upon application.

Open Shelter Summer House.




7-ft. × 5-ft. ... £9 6 0 8 ft × 6-ft. ... £11 6 0

Fitted with Revolving Gear if required, £4 extra.


Windows, Posts etc., painted two coats white paint. Portable and tenant's fixture

Creosoted Deal Fencing. £2 6 0 complete.




10ft. × 5ft. with Post.

Rustic Arches.




Price 15/-



Carriage forward.


Price 15/-

Double Entrance Gates. Price £9 18 0 complete.



Size 8ft. × 6ft., with 6in. × 6in. Pitch Pine Posts, with hinges.

The "BRITON" Motor Car House




	£	s.	d.		£	s.	d.
10×8 ...	11	19	0	16×10 ...	23	16	0
12×8 ...	14	18	0	18×12 ...	29	16	0
14×8 ...	16	14	0	20×12 ...	36	18	0
14×10 ...	20	6	0				

Good workmanship and durability. All sections marked for easy re-erection.

FOR SPECIFICATION (see page 41).

Artistic Garden Shelter.




Size, 8 ft. × 6 ft. ... £14 0s. 0d.

Other sizes quoted for.


Very neat and weather-proof. Roof covered with asbestos tiles.

The "RANLEIGH" Motor Car House.




	£	s.	d.		£	s.	d.
10×8 ...	12	12	0	16×10 ...	25	11	0
12×9 ...	16	1	0	18×10 ...	30	2	0
14×10 ...	20	14	0	20×12 ...	37	1	0

FOR SPECIFICATION (see page 41)



ROUGH CAST


Wood Portable Building.



	£	s.	d.
10-ft. × 8-ft. × 7-ft. 0-in. × 8-ft. 6-in. ...	12	7	0
12-ft. × 9-ft. × 7-ft. 6-in. × 9-ft. 0-in. ...	18	10	0
14-ft. × 10-ft. × 8-ft. 0-in. × 10-ft. 0-in. ...	25	9	0
16-ft. × 10-ft. × 8-ft. 0-in. × 10-ft. 0-in. ...	28	8	0
18-ft. × 12-ft. × 8-ft. 0-in. × 11-ft. 0-in. ...	37	16	0
20-ft. × 12-ft. × 10-ft. 0-in. × 13-ft. 0-in. ...	40	10	0

A strong building, suitable for Lecture Hall, Workshop, or other purposes.
FOR SPECIFICATION (see page 41)


Stable and Coach-house.



Constructed of 2-in. × 3-in. deal framework. Walls covered externally with $\frac{3}{4}$ -in. Tongued and grooved matchboarding. Roof covered with patent compressed felt which requires no tarring. Interior of stall lined to a height of 4ft. with tongued, grooved and beaded matchboarding. House doors ledge and braced. Door to stall raced. Windows as shown. Louvre to stall ingable end. Building treated with weather-proof composition.

	Length	Width	Ht. to eaves	Ht. to ridge	£	s.	d.
Suitable for	ft.	ft.	ft.	ft.			
1 Pony and Trap	14	10	7	10	20	19	0
1 Horse and Trap	15	12	8	11	27	18	0
2 Horses and Trap	20	12	8	12	37	16	0


Lean-to Greenhouse.



No.	Dimensions	£	s.	d.
1	7 ft. × 5 ft. ...	9	5	0
2	9 ft. × 8 ft. ...	12	12	0
3	10 ft. × 8 ft. ...	16	9	0
4	12 ft. × 8 ft. ...	20	5	0
5	15 ft. × 10 ft. ...	28	7	0

21-oz. glass cut to sizes, Packed complete.


Amateur's Greenhouse.




Dimensions	£	s.	d.
7-ft. × 5-ft. × 7ft. ridge and 4-ft. eaves ...	10	3	0
9-ft. × 6-ft. × 7ft. " 4-ft. " ...	12	17	6
10-ft. × 9-ft. × 7ft. 6-in. " 4-ft. " ...	17	7	0
12-ft. × 8-ft. × 8ft. " 5-ft. " ...	20	6	0
15-ft. × 10-ft. × 8-ft 6-in. " 5-ft. " ...	29	17	0

21-oz. glass cut to sizes. Packed complete.

Iron Building.




"PIONEER" Rustic Shelter.




Strongly recommended for invalids. Size, 7ft. long by 5ft. wide. Price £14 8 0
If with Revolving Gear, £4 10 0 extra.

The "VICTORIA" Shelter.




This design is arranged for a light and roomy Shelter House, and sure to give satisfaction. Casement windows as shown. Size 10ft x 6ft. Price £19 16 0

Dark Room.



Size 4 ft. x 3 ft.
£5 8 0


Photographic Studio.



	£	s.	d.	
12 ft. × 8 ft. ...	21	12	0	with floor.
14 ft. × 10 ft. ...	28	16	0	"

FOR SPECIFICATION (see page 41)

Amateur Studio.



	£	s.	d.	
10-ft. × 8-ft. ...	16	14	0	complete with floor.
12-ft. × 8-ft. ...	19	16	0	"
14-ft. × 10-ft. ...	27	0	0	"

FOR SPECIFICATION (see page 41).

ALL GOODS CARRIAGE PAID ENGLAND & WALES.

UNSOLICITED TESTIMONIALS.

111, Chestnut Street,
Ashington,
Northumberland.

8/2/26.
Dear Sirs,—The "Walton" I ordered from you arrived safely last week. Have now got it erected. *It is quite a charming little shed* and quite admired by my friends.—Yours faithfully,
GEO. HALL.

Holloway,
Nr. Matlock.

Dear Sirs,—I received motor house quite safe and sound. Wonderful value. Fits fine. Many thanks for your prompt attention. Wishing you every business success.—I remain, yours truly, W. HARDY.

Carisbrooke,
Reading Road,
Fleet, Hants.
9/2/26.

Dear Sir,—Will you please let me know price of rough-cast sheets. *I had 3-room cosy bungalow from you, and am very pleased with it.* I thought I would like rough-cast sheets for the outside now. Will you let me know how much it would be for the two sides and front. The bungalow measurement is 30ft. by 14ft. I don't want the sheets for the back.—And oblige, yours truly,
E. BREWER.

Rose View,
Clyne,
Nr. Rosolwen,
South Wales.

Dear Sir,—Just a line to let you know that we have got our bungalow up now and are living in it, and *we are highly satisfied with it.* If at any time we should have the opportunity of recommending you, we shall only be too pleased to do so.—I remain, yours truly, H. HARRISON.

The Nook,
Pimperne Village,
Blandford,
Dorset.

Dear Sir,—Many thanks for hut. We have now had same erected, and *we are very pleased with the workmanship.* *It is a good, strong, well-made one and several have admired it.* Now I wish to ask what you would make me

another similar one for, only 3ft. longer and 1ft. wider, viz., 12 x 8, with garage door; in fact, it is to keep a small car in, and then we could use it for other purposes. I don't suppose we would require it any more than 7ft. to the eaves, but you will know the height. Will you kindly let me have specification and lowest price by return if possible, and oblige.—S. RIGBY.

Please state when same would be completed after order, and oblige—S. R.

Duddington,
Stamford.
25/1/26.

Dear Sir,—I beg to thank you for forwarding the motor shed, which I received safe, and very pleased with the same.—Yours truly, C. CUNNINGTON.

Ratray,
Rumney Hill,
Cardiff.
1/2/26.


Dears Sirs,—I have recently received one of your "Maxim" garages through Messrs. Spurgeon, of Cardiff, and *am very pleased with same, especially the lighting from the double windows.*—Yours faithfully, T. STUART.

"The Willows,"
Queens Park,
Billericay.
21/1/26.

Dear Sirs,—I have received the goods that you have forwarded to me by rail, and thank you very much for glass. I shall just have enough, and *I am sure we shall like the bungalow very much when it is finished.* *It has been admired by many down here.*—Yours truly, JOSEPH SHERWIN.

10, Oaklands Road,
East Sheen, S.W.14.
21/12/25.

Dear Sirs,—With reference to the "Walton" garage which you delivered on Thursday last, I wish to inform you that *I have erected same and am very pleased with my purchase.* You omitted, however, to send the "run up," and I should be obliged if you would forward it as soon as possible.—Yours faithfully, H. G. HARRIS.



MOTOR GARAGE
16' X 10'

Erecting Plan for Garage.

SPECIFICATION
of
MOTOR CAR HOUSES
and
PORTABLE BUILDINGS
IN THIS LIST.

WALLS.—are clad with 1-in. tongued, and grooved weather boards, or $\frac{3}{4}$ -in. tongued and grooved matchboarding.

FLOORS.—1-in. tongued and grooved boards on 2 x 3-in. joists.

FRAMING.—All buildings over 8-ft. by 6-ft. of 2 x 3-in. deal

WINDOW.—1½-in. sash stuff.


GLASS.—21-oz. clear.

ROOFS.—¾-in. tongued, grooved and beaded matchboards.

FELT.—Pluvex (Ruberoïd Co.)

IRONMONGERY.—Doors hung on strong cross garnet, heavy tower bolts, deadlocks or rimlocks, and bolts for re-erecting.

STAIN.—All buildings treated with our nut-brown weather-proof composition.



Designed, Built and Erected by
**The South Western Appliance
 Co., Ltd.**


High Street,
 Fulham, S.W.6

⁰⁰ **ULU Wembley Rest House,**
 (fully licensed restaurant)
Malaya Section,
British Empire Exhibition.




Ceiling Plan of Olympia Bungalow —1926


BACK BEDROOM
3-6'x3' SHEETS
1½-6'x4' SHEETS




FRONT BEDROOM.
6-6'x3' SHEETS




BATH RM PASSAGE & KITCHEN
7-6'x3' AND 2-6'x4' SHEETS




BACK BEDROOM
3-6'x3' SHEETS
1½-6'x4' SHEETS




FRONT BEDROOM.
6-6'x3' SHEETS



LOUNGE
4-4'x4' AND 5½-6'x4' SHEETS



VERANDAH
3½-6'x4' SHEETS



Showing quantity of Asbestos Sheeting to be used and where to fix it. The sheets should be carefully cut as directed and the overlays placed as here shown, the dotted lines mark where there are no joints and are intended to complete the furnishing.




Illustration showing Foundation and Chimney made for one of our Bungalows. (1926 model)


The Super Simplex Loft-Ladder - £7 5s.



Super Simplex Type in down position ready for mounting.




Super Simplex Type, showing the ladder being pulled down by means of long arm.

MANTLE REGISTERS.

**No. 4 MANTEL REGISTER, WITH
LIFT-OFF HORIZONTAL BARS,
BRICK AT BACK.**

Sizes	24	×	38 ins.	30	×	42 ins
Shelf	29	×	5 „	36	×	5 „
Fire			12 „			14 „

Fine Cast 28/6 **44/8 each.**
Fret, 1/9 extra.
Painting, 5 p.c. extra.

No. 4a. TILED MANTLE REGISTERS.

**WITH MOVABLE CANO-
PY, CAST VERTICAL
BARS SMALL BRICK &
SINGLE SHELF.**

Prices, including Tiles		
Sizes	36 × 46 · 42 × 49 ins	
Shelf	6	7½ ins
Fire	15	17 „
Fine Cast	85/-	102/6
Extra :—		
Sectional Brick		10/-

BUNHILL FIREPLACE SUITE.


Height 46 ins. Width 30 ins. Projection 2½ ins. Shelf 33 × 4½ ins.

Bunhill Fireplace Suite in 4 × 4 ins. Tiles, Ornamental Insets, White-wood Shelf, 16 in. Fire, Loose hearth, Slabbed Curb,

Complete, as shewn but without Trivet **£9 12**
B.B. Trivet **10/-** extra.

We have a large assortment of Insets which may be varied to suit customers requirements.

LAVATORY OR BEDROOM SUITE.



A useful suite consisting of
No. 17 White
44
Cast Basin, 1 pair Cast Iron
Supports (to act as Towel
Rails), 1 pair of Brass Easy
Clean Hot and Cold ½-in.
Pillar Taps, 1¼ in. Slotted
Waste, Chain and Stay.

Complete Suite.	With 22 × 16 ins. Basin.	With 25 × 18 ins. Basin.	With 27 × 19 ins. Basin.
With Painted Brackets	53/-	76/-	82/8
With Porcelain Enam- elled White Brackets	62/9	85/9	92/6
Painted Brackets only	...	...	6/3 per pair.
Porcelain Enamelled Brackets only	...	...	16/- "

SINKS. BELFAST PATTERN.



Sizes.	Cane.	Cane and White.
24 × 16 × 7 ins.	32/-	41/4
30 × 18 × 7 "	44/-	54/8
36 × 20 × 7 "	59/8	74/4
24 × 16 × 10 "	45/4	56/-
27 × 18 × 10 "	56/-	72/-
30 × 18 × 10 "	61/4	77/4
36 × 18 × 10 "	94/8	108/-
36 × 20 × 10 "	100/-	114/8

Cast Brass Waste, with Brass
Plug, 3/- each.

We have a few second quality in stock at 15 per cent. less than above prices.


KITCHEN SINKS (FIRECLAY).

Fluted London Pattern.	Cane Glaze.	Cane and White.	Angular Pattern.	Cane.	Cane and White.
24 × 16 × 5 ins.	20/-	26/8	17 × 12 × 5 ins.	11/3	14/-
30 × 18 × 5 "	29/8	37/3			
36 × 20 × 6 "	46/8	58/6	20 × 14½ × 5 "	16/-	20/-

Note.—We have a few "Seconds in Stock at 15 per cent. less than above prices.
Solid Brass Slotted Waste, with Rubber Plug... .. 8/4 each.
Galvanised Cast Iron Trap, 2 ins., with Cleaning Eye, Plug and
Brass Grating 12/- "
Ditto, Screwed Outlets 14/- "
" 1½ ins., with Brass Grating only 9/3 "

Telephone: PUTNEY 4027 & 2771,

THE "O B T" CLOSET SUITE.



COMPLETE SUITE.

Consisting of 2 gallon "O B T" Silent Cistern, One Pair Fine Cast Cistern
Brackets, Galvanised Steel Flush Pipe, All White "Leadline" Pan, S or P
Trap, Real Mahogany Seat £4 6 0

"PRACTICAL" CLOSET SUITE.


Consisting of 2 gallon "Practical" or "Burlington" Cistern, One Pair Fine
Cast Cistern Brackets, Galvanised Steel Flush Pipe, Cane and White Pan,
Whitewood Seat £2 14 8 complete

ALL GOODS CARRIAGE PAID ENGLAND & WALES.

PORTABLE COOKING RANGES

The Famous "LARBERT"

A Strong, Efficient and Economical Range.



Height to Hob, 25 ins; Depth of Hob, 17 ins. Made Oven on right hand to order only.

Oven and Sham (No Register or Pipe).

Size of Range	...	...	...	...	20	22	24	26	28	30 ins
Size of Oven	...	...	...	...	9	10	10	12	12	14 ..

Prices 81/- 83/3 85/6 88/- 91/-

Size of Range	...	...	...	...	32	33	34	36	38	42 ins
Size of Oven	...	...	...	...	14	14	14	16	16	16 ..

Prices 95/6 96/6 99/- 100/- 106/- 112/6

Oven and Boiler, with Brass Tap (No Register Plate or Pipe).

Size of Range	...	28	30	32	33	34	36	38	42 ins.
Size of Oven	...	10	12	12	14	14	14	16	16 ..

Prices 100/- 102/6 105/- 106/3 107/6 110/- 118/6 125/-

Sheet Iron Covers and Pipes 4/- Extra.

Can also be supplied with High Pressure Boiler. In sizes 30, 33, 36


39 and 42 ins. at 58/- Extra to Oven and Sham Prices.

SPRING

1926

FOR THE

BUNGALOW



**BEST PORCELAIN ENAMEL (BRITISH MADE).
TAPER OR PARALLEL PATTERN.**

Price without Fittings.	2 in. Roll.		3 in. Roll.	
Length Inside ...	54 or 60 ins.	66 ins.	54 or 60 ins.	66 ins.
White Porcelain ...	118/6	125/-	130/-	136/-
Greenstone ...	121/6	128/-	133/-	139/-

Please note that the 4 ft. 6 in size Baths are stocked in Parallel Pattern only.

BRASS FITTINGS , consisting of one pair $\frac{3}{4}$ in. hot and cold Globe Cocks, $1\frac{1}{4}$ in. Overflow, $1\frac{1}{4}$ in. Trapped Waste with chain and stay					19/- per set
Ditto	Nickel Plated	...	...	...	27/6 ..
in. Brass Easy Clean Pillar Taps, through roll	...	...	...	...	26/6 ..
Ditto	Nickel Plated	...	...	...	33/- ..

ETERNIT

ASBESTOS-CEMENT

TILES

ARE PROOF against FIRE,
RAIN, WIND and TIME.

LOOK WELL and LAST WELL.

THE ORIGINAL and BEST.

COST LITTLE TO BUY AND LITTLE TO LAY.

COST NOTHING FOR UPKEEP,

BECAUSE THEY ARE EVERLASTING.


ETERNIT SHEETS

FLAT AND ROUGH CAST,

make artistic inexpensive

WALLS and CEILINGS.

SPEAKER'S ETERNIT.



THE SIGN OF EXCELLENCE.

G. R. SPEAKER & COMPANY

Eternit House, Stevenage Road,

LONDON, S.W.6.

UNSOLICITED TESTIMONIALS—Cont inued.

Westbrook Lodge,
Boxmoor. Herts.

The Building has arrived safely and
in good condition, for which we thank
you.—Yours faithfully,

A. CLAMP.

17, Tower Road,
St. Leonards-on-Sea.

Dear Sir, — Motor House and Earth
W. C. arrived in good condition, and
am very pleased with it.—Yours truly
J. R. UPLOST.

10, Peterborough Villas,
Fulham, S. W. 6.

Dear Sir, — We are delighted with
the St. Helier that was erected by your
men on Saturday last, and I think the
workmanship is both excellent and
prompt. We shall most certainly do our
best to recommend you.—

Yours faithfully,
E. M. S. AWLING

65, High Street,
Wimbledon, S. W. 19.

Dear Sir, — We have had the Bungalows
erected, and are very pleased with
it.—Faithfully yours,

L. GIBBARD.

Penponds,
86, Cecil Street,
Manselton, Swansea.

Gentlemen,—The 16ft. by 10ft. Walton
Motor House arrived here in good
condition on the 21st inst., and has
now been erected. I feel I should not
be doing my duty if I failed to write
to express my satisfaction with it. You
have certainly turned out a fine job —
I am, yours faithfully.

R. MILL.

"The Homestead,"
Hurst Lane,

Castle Bromwich,
nr. Birmingham.

Dear Sirs, — We are most pleased
with "Maxim" Garage. — Yours faithfully,
H. SIMMONS,

School Terrace,
Alston,
Cumberland.
29/3/26.

Dear Sirs,—I have to acknowledge
receipt of motor hut, in
good condition last Friday. It
has now been erected, and I wish
to say I am very well satisfied

with it and shall, of course, re-
commend you to my friends.
Thanking you,—Yours faithfully,
T. SARGINSON.

No 3 Bungalow,
Penyrheol,
nr. Caerphilly.

Dear Sir,—In reference to the Bungalow
which I purchased from you, I
must write and thank you for your
prompt attention that you showed to
us. We must thoroughly recommend
your Asbestos Buildings; they are quite
comfortable and cosy, and also a very
neat building after put together. And
we will also recommend your firm to
friends around us. So thanking you for
your kindness, —I am yours faithfully,
R. SAUNDERS.

128, Forest Road,
Loughton.

Dear Sirs, — We received the "De
Dion" Motor House on October 18th,
in good condition; we have erected it,
and are very pleased with same. Thank
you for your prompt attention to the
order.—Yours truly, G. SAVILLE.

"Fernley,"
Parkhill Lane,
Treboeth,
Swansea.

Sir, — Bungalow, received and erected,
corrected and satisfactory in every
detail. A very efficient means of solving
the housing problem. Expect a few local
orders soon.—Yours truly,
EDWIN MORGAN.

37, Cyprus Avenue,
Church End,
Finchley.

Dear Sirs, — Garage received and
erected; it looks a good substantial
building — even the builder compliments
you on wood, etc., employed.
—Yours truly, A. E. COPREY

Thorndyke,
Wentworth Road,
Barnet.
25/11/25.

Dear Sirs,—I received the
"Delholme" motor house this
morning and am very pleased with
it. It is an undoubted bargain.—
Yours faithfully, D. PLANK.

ALL GOODS CARRIAGE PAID ENGLAND AND WALES.

UNSOLICITED TESTIMONIALS.

15, Spring Cottages,
Mossby,
27/9/25.

Dear Sirs,—I have received the garage this morning, and have now got it erected, and am quite pleased with it.—Yours truly, W. HOLMES.

Estate Farm,
Frimington.

Gentlemen,—The motor house you sent has arrived in perfect condition, and we are very pleased with it.—Yours truly, J. BALE.
Peep O' Day School,

Devonshire Road,
Bognor.

Dear Sirs,—The building obtained from you is very satisfactory in every way and will prove of great use. All parts arrived in good condition, and now that it is erected, I am very pleased indeed with it.—Yours faithfully, THE PRINCIPAL.

The Wylde,
Warnedene Road,
Patcham, Brighton.

Gentlemen,—You will see by the above address that we are in residence at the bungalow purchased from you, and it is perfectly satisfactory.—Yours faithfully, GEO. B. HAIGH.

Pleasant View,
Clyde,
near Neath.

Dear Sirs,—I am recommending my friend, Mr. Harrison, of Resolven, he requires the same Bungalow as you sent me. Will you please write him giving him full particulars.—Yours obediently, J. R. GRAY.

62, Dutton Lane,
Eastleigh.

Dear Sir,—Have received Hut quite safely; we are very pleased indeed with it; looks quite nice up. Thanking you for same.—I remain, yours truly,

A. E. FOLLAND.

Extract from

"PICCADILLY ILLUSTRATED."

October 26th, 1925.

There are few matters of the present day in which it is more necessary to exercise extreme caution than in the buying of bungalows and other solutions for the housing problem. Thanks to the urgent demand for housing accommodation of any kind, there are many unscrupulous producers who are placing on the market bungalows and other buildings of the kind which seem to be cheap when their first price is considered, and which are eagerly bought by those who desire to invest their small capital in finding themselves somewhere to live. But in many cases these bungalows are but snares for the unwary, for there is nothing which requires more skill and judgment than the design of bungalows which shall be both economical in price and sound in planning and construction, and many buyers have found to their sorrow that the makers of their bungalows have had neither skill nor honesty in their work, and thus the bungalow has proved a very expensive and uncomfortable bargain.

Nevertheless, the field of bungalow design offers an immense scope for sound service to the public when it is placed in the right hands; and, despite the fact that so many things are more heard of in connection with the solving of the housing problem, the fact remains, that a more material contribution to that solution has been made by the manufacturer of mass-produced bungalows than by anyone else. The reputable and experienced type of firm in this industry, indeed, is producing very fine results, which, in our own view, will ultimately give the public furiously to think as to whether it is worth while to suffer the cost of bricks and mortar, as administered by profiteering builders, when so excellent a system of accommodation can be had at a moderate price.

Something of this thought occurred to ourselves, at any rate, when we had the opportunity of inspecting some of the work of

UNSOLICITED TESTIMONIAL—Continued.

that very interesting Company, the South Western Appliance Co., Ltd., who have their headquarters at High Street, Fulham, S.W.6, and whose name is well known to those who have visited the Ideal Homes Exhibition. This firm have for many years been specialising in the design and supply of the "ready to erect" bungalow, and their designs are interesting in the extreme, as showing the careful way in which they have gone into every detail of those twin problems—the erection of a first-class bungalow from the modern point of view, and the keeping of its price within limits which the majority of people can afford to pay.

Furthermore, unlike most of those who produce these buildings, the firm have not been content to produce two or three stereotyped models. On the contrary, they have a full list of bungalows numbering some two score and more, each of which is of individual design, and each specially planned to meet some particular need of the householder or the house buyer. Moreover, the firm's immense experience of building and selling these bungalows has given them a very fine insight into just what it is that the buyer desires of his bungalow; and thus they have been more than usually successful in meeting these needs, since they work from knowledge and do not design their buildings to suit the machinery and plant wherewith they are produced.

It is impossible here to enter into all the details of the many designs which the firm produce, and we must be content with saying that the firm issue a very fine list of plans, specifications and elevations which is free for the asking, and which ought to be seen by every house buyer. They are exhibiting at the next Ideal Homes Exhibition also, and their work is certain of attracting even more attention than was the case last year—when Press and public alike eulogised their very important work in no measured terms.

There are certain cardinal points, however, which must be mentioned before the work of this firm is understood at its true value to the home maker. One is, that

the firm have never been content to sacrifice beauty to utility, and that their bungalows are very far removed from the class usually produced, in which accommodation at a cheap rate has been the main consideration, and the elevations have as little beauty as the worst of "factory houses." Every bungalow produced by this firm is pleasing to the refined taste, in addition to being a sound and workmanlike job throughout.

The prices quoted, nevertheless, are remarkably low, for the simple reason that the firm have organised for production and sale on the large scale, and have carefully laid down the best of modern plant for production in every detail.

49, Heywood Street,
Bury, Lancs.

Dear Sir,—The "Delholme" I ordered from you arrived a few days ago. Everything was in good condition and went together very easily. I and various friends who have seen the Shed think it a bargain. If I hear of anyone wanting a Motor Shed I shall certainly give them your address.—Yours truly, R. GREGSON.

Brookheath,
Fordingbridge,
Hants.

The Allotment Shed arrived quite all right. I am very pleased with the Shed; it is quite satisfactory. E. MILLS.

30, Brewery Street,
Pembroke Dock,
S. Wales.

Building received, and am well satisfied. Many thanks. T. E. PANKES.

The Rectory,
St. Leonards-on-Sea.

The Motor House arrived safely this morning, and is in process of being erected. It looks quite satisfactory.

(Rev.) ARTHUR F. ALSTON.

Hillworth Paddox,
Rugby.

Gentlemen,—Thank you for Maxim Motor House received O.K. I am very pleased with it.—Yours, etc., J. BURSLEM.

REGISTERED TRADE MARK

